

Roof Lifecycle Cost Analysis

Hampton Roads market
October 6, 2026

Planned maintenance is projected to save the owner of a typical Hampton Roads school **\$1.34M** over the next 20 years.

About 35% less than reactive repair: \$990K lower spending plus \$352K more roof life at year 20. Range \$693K–\$1.75M from conservative to upside assumptions; \$698K in today's dollars at a 7% discount rate.

MARKET	PROPERTY	ROOF AREA	SYSTEM	AGE · CONDITION	NEW ROOF TODAY
Hampton Roads	K-12	120,000 sq ft	Modified bitumen	8 yrs · Good	\$960K

PAXSEAL NET COST

\$2.48M

\$2.39M spent + \$576K roof used – \$480K roof left

REACTIVE NET COST

\$3.83M

\$3.38M spent + \$576K roof used – \$128K roof left

REPAIR & STORM SAVINGS

\$1.63M

Unbudgeted repairs and storm damage avoided

ROOF PRICES

2× in 15 yrs

At 4.6%/yr, the long-run trend in commercial roofing costs

Cumulative roof spending, next 20 years

Nominal dollars. Vertical jumps are full roof replacements.



Roof life

When each scenario needs a new roof.



Where the savings come from

20-year totals

	PAXSEAL	REACTIVE	SAVINGS
PaxSeal fees	\$441K	—	-\$441K
Repairs paid by owner	\$234K	\$1.79M	+\$1.56M
Expected storm damage	\$140K	\$210K	+\$70K
Roof replacements	\$1.57M	\$1.38M	-\$190K
Cash spending	\$2.39M	\$3.38M	+\$990K
Current roof value used	\$576K	\$576K	—
Roof life left at year 20	-\$480K	-\$128K	+\$352K
Net 20-year cost	\$2.48M	\$3.83M	+\$1.35M

What this means

- 1

A later replacement. The next new roof moves from year 8 to year 11, leaving 10 years of roof life at year 20 instead of 2.
- 2

Smaller repairs. Emergency repairs run about 3.9× the planned rate in a school, and the PaxSeal fee covers half of planned repairs. Together that saves \$1.56M.
- 3

A predictable budget line. Emergency repairs become a fixed annual cost the board can plan for, and leaks stop closing classrooms.
- 4

The program pays for itself. Each \$1 of fees avoids about \$3.25 of other cash roof costs.

Local risk profile

Norfolk city, VA (51710)

Hurricane / tropical-storm wind

About 4.8 tropical storms or stronger within 50 nautical miles of Norfolk per 20 years (NOAA HURDAT2 1975–2024). Expected storm damage to this roof over 20 years is **\$140K** if maintained and **\$210K** with reactive repair only, before insurance. A documented maintenance history also helps when an insurer reviews a claim.

Hail

Strong wind

Tornado

Hurricane

Winter weather

Ice storm

FEMA National Risk Index rating

Relatively Low

Relatively Moderate

Relatively Moderate

Relatively Moderate

Relatively Moderate

Relatively Moderate

Key assumptions

The basis for each figure in this analysis.

ASSUMPTION	VALUE	BASIS
Roof life	20 / 15 yrs	Maintained / reactive. Industry life tables; maintenance adds ~5 yrs (NRC Canada, warranties)
Roof cost growth	4.6%/yr	BLS Producer Price Index, nonresidential roofing, 2007–2025
Replacement cost	\$8.00/sq ft	Hampton Roads contractor price ranges
Reactive repair cost	3× planned × 1.3	Industry estimates; ×1.3 for leak damage (school). PaxSeal fee covers half of planned repairs
Storm damage	0.44%/yr	Of roof cost, before insurance; ×1.5 if reactive. FEMA National Risk Index
PaxSeal fee	\$16,400/yr	Year 1, rising 3%/yr. Estimate; your proposal states the actual fee

Next step:

a roof assessment and a written PaxSeal proposal for this building. Call PAX Services Group at 1-855-729-7510 or email info@paxserv.com.

Estimates, not a quote.

Projections from Hampton Roads market research and industry data, in nominal dollars. The PaxSeal fee is an estimate; your proposal states the actual price. Net cost includes wear on the current roof, less roof life left at year 20; both roof-value figures are in today's dollars. Storm damage is before insurance.